



NOTES:

1. CYLINDER MATERIAL SHALL BE THINWALL ABS OR PVC PLASTIC PIPE.
2. TOP OF MONUMENT CORE SHALL BE FINISHED SMOOTH AND ROUNDED WITH NO CONCRETE ABOVE THE EDGE OF THE BRASS SURVEY MARKER.
3. THE BRASS SURVEY DISK SHALL BE PROVIDED BY THE PROJECT SURVEYOR.

COUNTY OF SONOMA DEPARTMENT OF TRANSPORTATION AND PUBLIC WORKS		
SURVEY MONUMENT		
DATE: MAY 2004	REVISED: JULY 2018	
APPROVED BY: JH	SCALE: NONE	DRAWING NO. 218